BRANDED SHOWROOM GRAPHICS

Lear Corporation 301 Logistics Center Drive Wentzville, MO 63385 Contact: Jessica Leonard Phone: 248.444.1010

eMail: jleonard@imbranded.com

2

Job No. 577744 April 18, 2022

GoBy





Installation Procedures

ArrivalTime

Arrival time has been scheduled with your Project Manager and the client. Please contact the PM if you are going to be later than the predetermined time so they can notify the client.

Inventory of Shipment

The installation team should conduct a physical inventory of all products shipped to the site. There are (2) color copies of the approved installation GoBy. The box containing the GoBys has a sticker on the outside. If there are any missing items or damage has occurred during shipping, please notify the PM immediately. Pictures should be taken of any damaged products. The PM will advise if we can install or a reprint will be necessary.

Walk Through with Onsite Contact

Upon arrival, a site walk-through should be conducted with the onsite contact using the supplied GoBy. Site issues, placements and any questions can be resolved immediately.

Upon installation completion, review the graphic placements and obtain the client's signoff of the Installation Completion Form. Note any issues or items that could not be installed and reason.

Installation Completion

Please do not leave the job site until after you speak to the PM


- 1. Contact the PM and provide status update, communicating any onsite changes to the approved GoBy or placement issues.
- 2. Confirm the lift can be called off.
- 3. Send completion photos of all graphics installed at the site. Photos should be sent to the PM within 24 hours of completion.
- 4. Have client sign the Installation Completion Form prior to departing the site. Note any issues or items that could not be installed and the reason.

NOTE: The Installation Completion Form and photos are required in order to process your invoice.

Project Manager: Erin Hemming

Phone: 866.717.4467

Email: ehemming@imbranded.com



PSVS 01 (30"w x 40"h) Z Mount, PVC 6mm



PSVS 02 (30"w x 40"h) Z Mount, PVC 6mm



Location: Lobby Area

Lear Corporation 301 Logistics Center Drive Wentzville, MO 63385



Contact: Jessica Leonard

Phone: 248.414.1010

eMail: ileonard@imbranded.com

Designer: MK

Job No. 577744 | PM: EH

PSVS 01 (30"w x 40"h) Z Mount PVC 6mm PSVS 02 (30"w x 40"h) Z Mount PVC 6mm



PSVS 3A (30"w x 40"h) Z Mount, PVC 6mm



PSVS 3B (30"w x 40"h) Z Mount, PVC 6mm



PSVS 3C (30"w x 40"h) Z Mount, PVC 6mm



Location: Conference Room 1

Lear Corporation 301 Logistics Center Drive Wentzville, MO 63385



Contact: Jessica Leonard

Phone: 248.414.1010

eMail: ileonard@imbranded.com

Designer: MK

Job No. 577744 | PM: EH

PSVS 3A (30"w x 40"h) Z Mount PVC 6mm PSVS 3B (30"w x 40"h) Z Mount PVC 6mm PSVS 3C (30"w x 40"h) Z Mount PVC 6mm



PSVS 4A (30"w x 40"h) Z Mount, PVC 6mm



PSVS 4C (30"w x 40"h) Z Mount, PVC 6mm



PSVS 4B (30"w x 40"h) Z Mount, PVC 6mm



PSVS 4D (30"w x 40"h) Z Mount, PVC 6mm



Location: Conference Room 2

Lear Corporation 301 Logistics Center Drive Wentzville, MO 63385



Contact: Jessica Leonard

Phone: 248.414.1010

eMail: jleonard@imbranded.com


Designer: MK

Job No. 577744 | PM: EH

PSVS 4A (30"w x 40"h) Z Mount PVC 6mm PSVS 4B (30"w x 40"h) Z Mount PVC 6mm PSVS 4C (30"w x 40"h) Z Mount PVC 6mm PSVS 4D (30"w x 40"h) Z Mount PVC 6mm



PSVS 5A (30"w x 40"h) Z Mount, PVC 6mm



PSVS 5B (30"w x 40"h) Z Mount, PVC 6mm



Location: Conference Room 3

Lear Corporation 301 Logistics Center Drive Wentzville, MO 63385



Contact: Jessica Leonard

Phone: 248.414.1010

eMail: jleonard@imbranded.com


Designer: MK

Job No. 577744 | PM: EH

PSVS 5A (30"w x 40"h) Z Mount PVC 6mm PSVS 5B (30"w x 40"h) Z Mount PVC 6mm



PSV 06 (192"w x 142"h) Wall Map Adhesive Wall Vinyl Covering



Will fill entire wall.

Location: Visitor Lobby

Lear Corporation 301 Logistics Center Drive Wentzville, MO 63385



Contact: Jessica Leonard

Phone: 248.414.1010

eMail: jleonard@imbranded.com

Designer: MK

Job No. 577744 | PM: EH

Live Area:

PSV 06 (192"w x 142"h) Wall Vinyl Covering



PSV 07 (600"w x 39.6"h) Adhesive Cut Red Letters - Shop Floor

See next page for install directions.

Making every drive better[™]

PSV 08 (120"w x 8"h) Adhesive Cut Red Letters - Visitor Lobby

Center horizontally on wall, 60"h from bottom.

Making every drive better™

Location: Shop Floor & Visitor Lobby

Lear Corporation 301 Logistics Center Drive Wentzville, MO 63385



Contact: Jessica Leonard


Phone: 248.414.1010 eMail: ileonard@imbranded.com

Designer: MK

Job No. 577744 | PM: EH

PSV 07 (600"w x 39.6"h) Cut Red Letters PSV 08 (120"w x 8"h) Cut Red Letters





PSVS 09 (30"w x 40"h) Z Mount, PVC 6mm



PSVS 10 (30"w x 40"h) Z Mount, PVC 6mm



Location: Hallway

Lear Corporation 301 Logistics Center Drive Wentzville, MO 63385



Contact: Jessica Leonard

Phone: 248.414.1010

eMail: ileonard@imbranded.com

Designer: MK

Job No. 577744 | PM: EH

Live Area:

PSVS 09 (30"w x 40"h) Z Mount PVC 6mm PSVS 10 (30"w x 40"h) Z Mount PVC 6mm



PSVS 11 (30"w x 40"h) Z Mount, PVC 6mm



PSVS 12 (30"w x 40"h) Z Mount, PVC 6mm



PSVS 13 (30"w x 40"h) Z Mount, PVC 6mm



Location: West Area Live Area: Page 12

Lear Corporation 301 Logistics Center Drive Wentzville, MO 63385



Contact: Jessica Leonard Phone: 248.414.1010

eMail: ileonard@imbranded.com

Designer: MK

Job No. 577744 | PM: EH

PSVS 11 (30"w x 40"h) Z Mount PVC 6mm PSVS 12 (30"w x 40"h) Z Mount PVC 6mm PSVS 13 (30"w x 40"h) Z Mount PVC 6mm



PSVS 14 (30"w x 40"h) Z Mount, PVC 6mm



PSVS 15 (30"w x 40"h) Z Mount, PVC 6mm



PSVS 16 (30"w x 40"h) Z Mount, PVC 6mm



Location: Hallway

Lear Corporation 301 Logistics Center Drive Wentzville, MO 63385



Contact: Jessica Leonard

Phone: 248.414.1010

ileonard@imbranded.com eMail:

Designer: MK

Job No. 577744 | PM: EH

Live Area:

PSVS 14 (30"w x 40"h) Z Mount PVC 6mm PSVS 15 (30"w x 40"h) Z Mount PVC 6mm PSVS 16 (30"w x 40"h) Z Mount PVC 6mm





INSTALLATION COMPLETION FORM

1 SITE INFORMATION Customer Name: Job#: Address: Site Phone Number: Phone: Alternate Site Contact Name: Phone: Alternate Site Contact Name: Phone: Phone: Phone: Alternate Site Contact Name: Phone: Phone: Phone: Phone: Phone: Phone:	
Site Arrival Date:Time:	-
2 PRE-INSTALLATION PROCEDURE Introduction to Site Contact Verification of all products and equipment exist on-site Retrieval of Graphic GoBy and/or Millwork Plan from the materials	
Verify graphic/millwork areas are cleared for installation Walk site with Site Contact and review all areas for graphics/millwork Pre-installation walk-through completed with: Name: Title:	5 SITE CONTACT JOB NOTES
POST-INSTALLATION PROCEDURE All graphics/millwork have been installed to match Graphic GoBy/Millwork Plan Graphics/Millwork installed in different areas per Site Contact Direction (List changes in "Installer Job Notes" section) All graphics/millwork checked for quality All debris, trash, shipping materials, etc. are disposed of properly and work areas are clean after install	
Use chart below for Millwork sign off for each room/location	6 INSTALLATION SIGN-OFF
Room Name/Number Accepted Declined Notes	Walk entire site with Site Contact after Installation Checklist is complete I agree that the installation is either complete or is complete with the exception of the items listed in the notes above, which will be addressed in a timely manner.
	Lead Installer:
	Site Contact: Signature Printed Name Date
Please use chart(s) on next nage for additional locations not already listed	Plassa leave a conv of this completed signed document with the Site Contact when possible